8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Details of work	Number	Dimensions			Content
Girders for Ground Floor—					
Centre room	4	32′	7½″	24″	
For A and B room	2×12	34′	7½″	24″	
For Central Hall	2×6	33′	7½″	24″	
For Porch	2	22′	6″	14″	
Double Girders at entrance	2	32′	7½″	24″	
Girders for First Floor—					
Central Hall	4	32′	7½″	20″	
A and B Halls	2×12	34′	7½″	20″	
C. Hall	2×6	32½′	7½″	20″	
Porch	2	22′	6″	14″	

C. VIJAYARANGAM NAIDU,
Executive Engineer.

TUMKUR DIVISION.

Dated 19th February 1917.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 15th March 1917, for deviating Yediyur-Tiptur road below Nonavinkere tank bund, Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1918.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M., on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for deviating Yediyur-Tiptur road", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Serial No.	Items of work	Per	Quantity
1	Earthwork embankment including carting, ½ mile lead from either side with watering, forming and consolidating, etc.	C. yd.	5,265
2	Cutting earthwork and using it to embankment including forming	„	3,085
3	Turfing	S. yd.	3,305
6	Collecting rough metal including carting and stocking, etc.	C. yd.	1,379
7	Collecting, breaking and stocking field metal	„	690
8	Carting metal, 2 miles lead	„	690
9	Collecting, carting and stocking gravel	„	689
10	Spreading, watering and consolidating rough metal	„	1,379
11	Do field metal	„	690
12	Do gravel	„	689
12	Collecting and spreading sand	„	18
13	Construction of a tunnel	Lump sum	Rs.
14	Compensation for lands	„	„
15	Removing and fixing mile and furlong stones	„	„
16	Constructing drains and revetting slopes of bund	„	„
17	Royalty for metal and gravel	„	„

C. KRISHNA IYENGAR,
Executive Engineer.